

Miami Shores Village**Addendum 1****No. 2021-02-01****“N.E. 96th Street from N.E. 2nd Ave to N.E. 10th Ave
Roadway Improvements”**

The following three (3) items described below shall be included as part of the required documents in the bid proposal:

1) BID GUARANTY

The bid must be accompanied by a Bid Guaranty which shall be for an amount equal to five percent (5%) of the proposal, and at the option of the bidder may be a certified check, cashier's check, or bid bond. Cash deposits will not be accepted. The Guaranty shall be forfeited if the successful bidder fails to enter into a contract in the form shown within ten (10) working days of the Notice of Award of the Contract. The checks and bid bonds of all except the three (3) lowest bidders will be returned immediately after the opening of bids, and the remaining checks or Bid Bonds will be returned within ten (10) working days after the signing of the contract by the successful bidder.

2) PERFORMANCE AND PAYMENT BONDS

Within ten (10) working days of the award of the Contract, the successful bidder shall furnish a Performance and a Payment Bond guaranteeing the faithful performance of his contract and for the payment of all persons performing labor or furnishing materials in connection therewith. Each bond shall be in the amount of one hundred percent (100%) of the Contract price.

3) PAY ITEMS & QUANTITIES UPDATED:**N.E. 96th STREET FROM N.e. 2nd AVENUE TO N.E. 10th AVENUE - ROADWAY IMPROVEMENTS
VILLAGE OF MIAMI SHORES RFP 2021-02-01**

PAY ITEM	FDOT PAY ITEM	PAY ITEM DESCRIPTION	UNIT	PLAN QUANTITY	UNIT PRICE	PRICE
1	0110-1-1	Clearing and Grubbing	LS	1		
2	0104-10-3	Sediment Barriers (Silt Fence)	LF	100		
3	0104-18	Inlet Protection System	EA	44		
4		Cleaning/Destiling Exist. & Prop. Storm Sewer	LS	1		
5	0110-4-A	Removal of Existing Concrete	SY	136		
6	0285-711	Optional Base Group 11 (12" Limerock LBR 100, for Trench Reconstruction)	SY	271		
7	0327-70-1	Milling Existing Asphalt Pavement (1" Average)	SY	31,413		
8	0337-7-80	Asph Conc Friction Course Traffic B (FC-9.5)	TN	1,728		
9	0425-1202	Curb Inlet Type 9 with Round Bottom >10'	EA	8		
10	0425-2-42	Manhole, P-7, >10'	EA	2		
11	0425-1-54 1	Gutter Inlet - Type V >10'	EA	1		
12	0425-1-432	Inlet Drainage - Type 3 J Bottom >10'	EA	1		
13	0425-5	Manhole-Ajust, Existing Sanitary & Storm Manhole Rim Elevation	EA	10		
14	0443-70-4	French Drain, 24"HDPE	LF	480		
15	0430-115-118	Pipe Culvert, round Shape 18" HDPE S/CD	LF	130		
16	0522-002	Concrete Sidewalk for Curb Ramps, 6" thick	SY	136		
17	0527-002	Detectable warnings	SF	141		
Subtotal Roadway						
PAY ITEM	FDOT PAY ITEM	PAY ITEM DESCRIPTION	UNIT	PLAN QUANTITY	UNIT PRICE	PRICE
1	0706-3	Retro-Reflective Pavement Markers	EA	369		
2	0711 - 11123	Thermoplastic, Std, White, Solid, 12"	LF	1,937		
3	0711 - 11124	Thermoplastic, Std, White, Solid, 18"	LF	38		
4	0711 - 11125	Thermoplastic, std, white, solid, 24"	LF	362		
5	0711 - 11160	Thermoplastic, standard, white, message or symbol	EA	4		
6	0711 - 11170	Thermoplastic, standard, white, arrow	EA	5		
7	0711 - 16101	Thermoplastic, Std-0th, White, Solid, 6"	GM	1,837		
8	0711 - 16131	Thermoplastic, std-0th, White (10-30) skip, 6"	GM	0,303		
9	0711 - 16201	Thermoplastic, Std-0th, Yellow,Solid, 6"	GM	1,870		
Subtotal Pavement Marking and Signage						
TOTAL						
		Mobilization	LS	1		
		Maintenance of Traffic	LS	1		
		Permitting Allowance	LS	1		
		Contingency (Do Not Bid)	LS	1	\$ 60,000.00	\$ 60,000.00
Subtotal						
PROJECT TOTAL (IN FIGURES)						

*****Bidders must sign a copy of this addendum as acknowledgment of receipt and must include in the proposal.**